

SUMMARY OF QUOTATION

Title : TO REPLACE SIGNAGE FOR HEAXAGON DISPLAY AND ARCH PANEL AT MINISTRY OF HEALTH HEADQUARTER.

Page 1 Of 2

No	Description	Quantity	Unit	Amount		
				Rate	\$	¢
	<p>Note : The contractor shall carry out site visit inspection and take into account all aspects and conditions of site before submitting his quotation. The contractor must fill this schedule at the time of tendering. Contractor having submitted their prices are considered as having visited the site. No claims for additional payment will be entertained on the ground of misunderstanding or misinterpretation of the conditions, measurement etc.</p> <p><u>SCOPE OF WORKS</u></p>					
1.0	To fabricate and install illuminated Vision signage (Jawi, Malay and English) in stainless steel 20mm thick build up with 10mm clear acrylic based. Work shall include to dismantle existing signage and make good any effected. Location: wall behind Reception counter	1.0	Lot			
1.1	To supply and install new paper display poster using 420gsm PETfilm with UV full color printing at existing hexagon display.	26.0	No			
1.2	To supply and install new hexagon display box as per existing design and material c/w with any other accessories require.	6.0	No			
1.3	To supply and install new paper display poster using 420gsm PETfilm with UV full color printing at existing rectangular display. Location: behind the reception counter. Size: 1100mm (L) x 1460mm (H)	1.0	No			
1.4	To dismantle existing signage ' Bersama Ke Arah Warga Sihat ' and LED strip light. Location: external main entrance arch panel.	1.0	Lot			
1.5	To supply and install new slogan vision ' Warga Yang Lebih Sihat ' using stainless steel build-up lettering with illuminated and including all necessary fixing accessories and termination on electrical work. Dimension of letter shall suit the existing area or as per existing. Location: external main entrance arch wall.	1.0	Lot			
TOTAL AMOUNT TO BE CARRIED FOWARD						

SUMMARY OF QUOTATION

Title : TO REPLACE SIGNAGE FOR HEAXAGON DISPLAY AND ARCH PANEL AT MINISTRY OF HEALTH HEADQUARTER.

Page 2 Of 2

No	Description	Quantity	Unit	Amount		
				Rate	\$	¢
1.6	<p>Refurbish the existing signage Arch panel. The scope shall include, but not limited to:</p> <ul style="list-style-type: none"> Remove existing paint with paint remover Apply undercoat layer using AlphaMax Epoxy Primer or approved equivalent. Spray paint with appropriate and approved paint c/w 2K and above lacquer clear coat. State Brand: Colour selection as to match existing or S.O Instruction. 	1.0	Lot			
TOTAL AMOUNT						